

**CITY OF WILDWOOD  
UTILITIES DEPARTMENT  
2021-2022  
CONSTRUCTION COST UNIT PRICES**

**SANITARY SEWER**

<b><u>Force Main C-900, DR-18 (4'-6' BURY)</u></b>	<b><u>Units</u></b>	<b><u>Unit Cost</u></b>
(costs include fittings, restraints, etc.)		
4"	LF	\$ 45.00
6"	LF	\$ 59.00
8"	LF	\$ 70.00
12"	LF	\$ 100.00
<b><u>Gate Valves</u></b>		
(costs include restraints, etc.)		
4"	unit	\$ 1,000.00
6"	unit	\$ 1,350.00
8"	unit	\$ 2,400.00
12"	unit	\$ 3,500.00
Air Release Valve	unit	\$ 4,500.00
4" sewer lateral (complete)	unit	\$ 700.00
6" sewer lateral (complete)	unit	\$ 1,000.00
<b><u>4' dia. Manholes (complete, in-place)</u></b>		
0'-6' bury	unit	\$ 2,750.00
6'-10' bury	unit	\$ 3,500.00
10'-14' bury	unit	\$ 5,000.00
14'-20' bury	unit	\$ 7,000.00
<b><u>8" Collection Piping (SDR-35)</u></b>		
4'-6' deep	LF	\$ 42.00
6'-10' deep	LF	\$ 50.00
10'-14' deep	LF	\$ 62.00
14'-20' deep	LF	\$ 75.00
<b><u>12" Collection Piping (SDR-35)</u></b>		
4'-6' deep	LF	\$ 60.00
6'-10' deep	LF	\$ 73.00
10'-14' deep	LF	\$ 85.00
14'-20' deep	LF	\$ 100.00

**Jack and Bore**

12" Casing Pipe	LF	\$	600.00
18" Casing Pipe	LF	\$	750.00
24" Casing Pipe	LF	\$	1,000.00
Jacking and Receiving Pits	Unit	\$	5,500.00

**Lift Station Costs**

Individual Grinder Station	Unit	\$	20,000.00
Duplex Grinder Station (.5hp - 5hp)	Unit	\$	75,000.00
Duplex Station per COW Detail (5hp - 15hp)	Unit	\$	350,000.00
Triplex Station per COW Detail (15hp - 30hp)	Unit	\$	500,000.00

**Grease Traps**

Grease Traps (500-1000 gal)	Unit	\$	5,500.00
Grease Traps (1000-2000 gal)	Unit	\$	10,000.00